



Note:-
All existing trees and planting
to remain unchanged

Note:-
All existing trees and planting
to remain unchanged

Existing Tree Survey Report				
Tree Number	Species	Height (Crown Height)	Spread	Girth (Dia)
T1	Ash	17.0m	8.0m	0.5m
T2	Ash	26.0m	12.0m	1.1m
T3	Ash	16.0m	8.0m	0.5m
T4	Ash	16.5m	12.0m	0.55m
T5	Hazel	8.5m	7.0m	0.55m
T6	Lime	7.5m	5.0m	0.5m
T7	Lime	10.5m	8.0m	0.6m
T8	Lime	11.5m	10.0m	0.6m
T9	Sycamore	18.5m	12.2m	0.55m
T10	Lime	14.5m	8.0m	0.5m
T11	Cherry (Multi)	5m	10.0m	0.7m
T12	Cherry (Multi)	5m	6.0m	0.5m
T13	Poplar	5.5m	4.8m	0.2m
T14	Leylandi	9m	5.0m	0.5m
T15	Lime	19.6m	22.0m	1m
T16	Willow	4.5m	3.0m	0.15m
T17	Willow	4.5m	3.0m	0.15m
T18	Willow	4.5m	3.0m	0.15m
T19	Willow	4.5m	3.0m	0.15m
T20	Willow	4.5m	3.0m	0.15m
T21	Common Beech	11.5m	10.0m	0.5m
T22	Yew	4.5m	7.0m	0.4m
T23	Leylandi	6.5m	4.0m	0.25m
T24	Horse Chestnut	10.3m	8.0m	0.55m

KEY

Existing Trees

Root Protection AreasProposed TreesTrees to be removed

Tree Protection Measures

Protective fencing should be erected as per the Tree Protection Plan at the linear distances specified in the Tree Survey Schedule prior to the commencement of any works on site.

The default specification should consist of a vertical and horizontal scaffold framework, well braced to resist impacts, as illustrated in Figure 7.2 (see below).

All-weather notices should be attached to the fencing

1 Standard scaffold poles

2 Uprights to be driven into the ground

3 Poles secured to uprights with wire ties and, where necessary, standard scaffold clamps

4 Weldmesh wired to the uprights and horizontals

5 Standard clamps

6 Wire twisted and secured on inside face of fencing to avoid easy dismantling

7 Ground level

8 Approx. 0.6m driven into the ground

Rev A Drawing revised 21-12-2020

Residential | Commercial | Industrial

ARCHITECTURAL SERVICES

Little Bishops Cottage Staunt Road Frithville Boston
Lincolnshire PE22 7ED

APPLICANT NAME: Mr S Allen		
PROPOSAL: Proposed Residential Dwelling Burton Corner Sibsey Road Boston Lincolnshire	DATE: October 2020	SCALE: 1:200
DRAWING TITLE: Tree Survey Plan Root Protection Measures	DRAWING NO: 12-424-07	REVISION: A